

2.5. Ish hajmlarini bajarilishiga qarab tartibga bo'linishi

№ t/r	Ishlar nomi	Ulch.b irl.	Obod	Obod	Obod	Obod	Jami
			МФЙ ariq-1	МФЙ ariq-2	МФЙ ariq-2-1	МФЙ ariq-3	
1	2	3	4	5	6	7	8
1	Eski tepaliklarni T-130 o.k. bulldozer bilan 1 guruhli tuproqni qirqib avtotransportga ortish, ko'tarmaga to'kish (1 km ga)	мн/м³	71/43				71/43
2	Eski tepaliklarni T-130 o.k. bulldozer bilan 1 guruhli tuproqni qirqish	м³			9		9
3	Кутарма килинадиган жойларда 20 см усимлик катлами киркиш, 1гр.	м³	127	70		554	751
4	Kanal o'zanini bir kovshli 0,65 m³ li ekskavator bilan guruhli tuproqda qazish va avtotransportga ortish, ko'tarmaga to'kish (1 km ga)	мн/м³	28/17	21/13		294/178	300/ 182
5	Kanal o'zanini bir kovshli 0,65 m³ li ekskavator bilan guruhli tuproqda qazish	м³		15	151		192
6	Kanal o'zanidan chiqqan 1-guruhli tuproqni T-130 o.k buldozer bilan 10 metrqa tekislash 50%	м³		7	76		97
7	Kanal polkasini bir kovshli 0,65 m³ li ekskavator bilan 1 guruhli tuproqda qazish va avtotransportga ortish, bir qismini ko'tarmaga to'kish (1 km ga)	мн/м³		167/101		208/126	282/171
8	Rezervdan kutarmani shu ekskavator bilan 1 guruhli tuproqda qazish va avtotransportga ortish, ko'tarmaga to'kish (1 km ga)	мн/м³	328/ 199			891/540	1219/ 739
9	Ko'tarmani suv sepib sifatli zichlash, 1-guruhli tuproq	м³	259	114		844	1217
10	Yo'lni sozlash va otval ishari	м³	259	114		844	1217

11	Beton ostini qo'l kuchi bilan tekislash, grunt 1gr.	m^2	559	366	1290	4139	6354
12	Kanal o'zaniga beton yotqizish, Beton B12.5 8 sm	m^3	44,72	29.24	103,20	331,1	508,26
13	Armatura BP-1 130x130, 5 mm	m/kg	6240/ 961	4080/ 628	14400/ 2218	46200/ 7115	70920/ 10922
14	Poliizol 3mm	m^2	20	13	46	148	227
14	Poliizol 1.8 mm	m^2	60	39	138	591	828